

KSCMMC LTD

DEPARTMENT OF CIVIL ENGINEERING

QUOTATION SCHEDULE-PAINTING WORK

NAME OF WORK: KSCMMC LTD- Construction of DF Factory Shed for Coirfed Thavam

ITEM NO.	DESCRIPTION	QTY	UNIT	RATE (INCLUDING GST 18%)	AMOUNT	QUOTED RATE	QUOTED AMOUNT
2.WORK SHED							
1	(VIDE ITEM 13) 13.43.1 Applying one coat of water thinnable cement primer of approved brand and manufacture on wall surface:Water thinnable cement primer	26.220	sqm	82.32	2158		
2	(VIDE ITEM 14) 13.60.1 Wall painting with acrylic emulsion paint of approved brand and manufacture to give an even shade:Two or more coats on new work	26.220	sqm	176.41	4625		
3	(VIDE ITEM 15) 13.62.1 Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade:Two or more coats on new work over an under coat of suitable shade with ordinary paint of approved brand and manufacture .	157.991	sqm	243.01	38393		
3.TOILET							
1	(VIDE ITEM 12) 13.43.1 Applying one coat of water thinnable cement primer of approved brand and manufacture on wall surface:Water thinnable cement primer	79.74	sqm	82.32	6564		
2	(VIDE ITEM 13) 13.60.1 Wall painting with acrylic emulsion paint of approved brand and manufacture to give an even shade:Two or more coats on new work	79.74	sqm	176.41	14067		
3	(VIDE ITEM 15) 13.61.1 Painting with synthetic enamel paint of approved brand and manufacture to give an even shade:Two or more coats on new work	2.5	sqm	166.69	417		
4. ROTARY SHED							
1	(VIDE ITEM 12) 13.43.1 Applying one coat of water thinnable cement primer of approved brand and manufacture on wall surface:Water thinnable cement primer	7.7	sqm	82.32	634		
2	(VIDE ITEM 13) 13.60.1 Wall painting with acrylic emulsion paint of approved brand and manufacture to give an even shade:Two or more coats on new work	7.7	sqm	176.41	1358		
3	(VIDE ITEM 19) 13.61.1 Painting with synthetic enamel paint of approved brand and manufacture to give an even shade:Two or more coats on new work	46.194	sqm	166.69	7700		
5. MACHINE FOUNDATION							

1	(VIDE ITEM 7) 13.43.1 Applying one coat of water thinnable cement primer of approved brand and manufacture on wall surface:Water thinnable cement primer	33.045	sqm	82.32	2720		
2	(VIDE ITEM 8) 13.60.1 Wall painting with acrylic emulsion paint of approved brand and manufacture to give an even shade:Two or more coats on new work	33.045	sqm	176.41	5829		
				TOTAL	84466		

Total quoted amount in words

I..... (Name & Address) do hereby agree that,I wiil execute the work at the above quoted rates .

Date
Place

Name & Signature of Contractor